



# ***OPERATING INSTRUCTIONS***

**CUSTOMER: DUPONT DE NEMOURS**

**MODEL: CL 0-300**

**Serial number: 201 003 0**

**VOLTAGE: 400 V / 50Hz / 3Ph + N + G**

**ORIGINALLY PRINTED  
ON: 12/04/2011**

This document is the English translation of the referenced BIA Climatic Chamber originally provided to DuPont in 2011. Please excuse any grammatical errors as a result of translation. If any discrepancies are found, the original French document takes precedence.

The information contained in this document is **CONFIDENTIAL**, and for the use of the intended recipients, and not to be shared with third parties without expressed written agreement from BIA or its assigned representatives.

For technical support or any additional information, please contact BIA North America at +1 248 790 8327, E-mail: [info@bia-na.com](mailto:info@bia-na.com), or BIA headquarters at [www.bia.fr](http://www.bia.fr).



ZA les Boutries, rue de l'Hautil, 78700 Conflans Sainte Honorine, France

Tel +33 1 3490 2222

[www.bia.fr](http://www.bia.fr)

E-mail: [bia.clim@bia.fr](mailto:bia.clim@bia.fr)

# CONTENTS

- 1. INSTALLATION .....5**
  - 1.1. INCOMING CHECK.....5
  - 1.2. LOCATION .....5
  - 1.3. ELECTRIC CONNECTIONS .....5
  - 1.4. WATER CONNECTION .....6
    - 1.4.1. *Condensation water* .....6
    - 1.4.2. *Humidification pipe water*.....6
    - 1.4.3. *Cooling water*.....6
    - 1.4.4. *Measuring the humidity*.....6
- 2. PROCEDURE .....7**
- 3. THE CONTROLLER .....8**
  - 3.1. CONTROL PANEL.....8
  - 3.2. MENU TREE STRUCTURE .....9
    - 3.2.1. *MAIN Menu*.....9
    - 3.2.2. *MAINTENANCE Menu*.....9
    - 3.2.3. *MANUAL CONTROL Menu*.....10
    - 3.2.4. *MANUAL CONTROL Screen Page*.....11
    - 3.2.5. *PROGRAMMED CONTROL Menu* .....12
    - 3.2.6. *PROGRAMMED CONTROL Screen Page*.....13
    - 3.2.7. *PROGRAMMING Menu*.....14
    - 3.2.8. *PROGRAM ENTRY Menu*.....15
    - 3.2.9. *INIT Menu* .....16
    - 3.2.10. *CUSTOMISATION Menu* .....17
  - 3.3. MESSAGES .....18
- 4. MAINTENANCE .....19**
  - 4.1. GENERAL MAINTENANCE .....19
  - 4.2. CALIBRATION .....19
- 5. USER INTERFACES .....20**
- 6. TECHNICAL SPECIFICATIONS .....21**
- 7. ELECTRIC FILES .....22**

## ***WARRANTY***

Thank you for purchasing a BIA climatic chamber.

We have built it according to the accepted standards of excellence, and it has been carefully tested before being shipped to you. In order to use it to its fullest extent, we invite you to follow the instructions provided in this document.

If, despite all our efforts, a problem should arise during normal usage, the appliance has a 12 months warranty from date of original acceptance, covering spare parts (return by yourself)

# ***DECLARATION OF CONFORMITY***



The manufacturer:

**BIA**  
**Z.A Les Boutries**  
**8, rue de l'Hautil**  
**78700 CONFLANS STE HONORINE - FRANCE**

Declares that the following equipment:

***Model: CL 0-300***

***Serial number: 201 0030***

Is in compliance with the directives

89/392/EEC amended by 93/68 EEC  
89/336/CEE  
73/23/CEE

and with the applicable relevant standards.

Made out in Conflans Ste Honorine, on 12/04/2011

F. NAMOUN  
Director



# **1. Installation**

## **1.1. Incoming check**

If need be, a quick check of the climatic chamber should allow you to make the feedback to the carrier in case of shipping related damage.

For loading and unloading purposes, we recommend that you use a fork-lift truck.

For large climatic chambers provided with frames featuring angles, the tip of the forks should be placed under an angle.

**IT IS ABSOLUTELY FORBIDDEN TO USE LIFTING BLOCKS OR HOISTING SLINGS**, which would otherwise damage the controls of the climatic chamber.

## **1.2. Location**

Provide for necessary space around the climatic chamber in order to carry out the required maintenance operations.

## **1.3. Electric connections**

Make sure that the main connection voltage is the same as the voltage mentioned on our manufacturer's identification plate.

The guarantee applies when the mains voltage fluctuations do not exceed  $\pm 5\%$  of the rated voltage.

The incoming lines shall be able to provide the required power for the climatic chamber without any drop in voltage.

The power cable is two meters long. We do not provide the plug-in outlet due to the wide variety of models used.

**The yellow / green wire is the earth cable.**

**Wire marked 1 is Neutral**

## **1.4. Water connection**

### **1.4.1. Condensation water**

Condensates either from inside the tank or from defrosting the refrigerating tubes, or from emptying the humidifier and its standby tank, are channeled to a discharge pipe located behind the climatic chamber. This pipe has no mark on it. It shall be connected to a discharging hole.

### **1.4.2. Humidification pipe water**

Deposit of scale in the piping system is the main cause of malfunction of this related sub-system. We therefore recommend that you use distilled water or, failing that, de-mineralized water, but not de-ionized water.

The standby tank is filled either automatically by the pressurized piping system (<3 bars), or manually.

The supply pipe in the automatic mode is identified by the label « EAU DEMI ».

For the automatic filling operation, the standby tank is located in the lower part of the control cabinet.

Draining the humidification piping system is carried out using « quick taps » located on the discharge pipes inside the control cabinet.

No energy is required for draining the whole system.

The piping system must be drained in case of frost, or when the system is moved, or if the climatic chamber is not used for an extended period of time.

### **1.4.3. Cooling water**

The connections input/output are done on the back of the unit, using coupling unions 15/21. Adhere to the reference mark registered on piping.


Water, free from particles higher than 500 µm, must be provided under a pressure higher than 2 bars. The temperature should not exceed 25°C. The power rejected is 5,3Kw

The unit is equipped with a pressure-controller valve which controls the water flow according to the real needs for the unit.

### **1.4.4. Measuring the humidity**

Capacitive probe VAISALA, model HMT337

## 2. Procedure


- Connect the climatic chamber to a 400 V / 50Hz / 3Ph+N+G, 12A mains power supply.
- Fill the standby tank through its filler hole located on the left side of the climatic chamber or connect the distilled water pipe to a pressurized supply.
- Switch the I/O control to I position.
- Display the set points for temperature and humidity. For that purpose, refer to paragraph « Controller  ».




**Warning: burning hazards.**

**It is strongly recommended to use gloves when handling test specimens inside the climatic chamber.**

## 3. The controller

### 3.1. Control Panel




- 1 Field featuring 4 lines of 20 characters.  
This displays the menus or the data relating to the climatic chamber control.
- 2  Key      It aborts the current processing and displays the main menu.  
It stops the climatic chamber.
- 3  Key      It turns the light inside the climatic chamber on and off.
- 4  Key      In a menu type screen page you can, it selects the function which blinks.  
In a parameter-setting screen page, it validates the value of the field which blinks and goes to the next field.
- 5 « SURFER » key      In a menu type screen page, it scans the fields of this menu.  
In a parameter-setting screen page, it enables adjustment of the values, the units, or the state of the relays.




## 3.2. Menu tree structure

### 3.2.1. MAIN Menu



### 3.2.2. MAINTENANCE Menu



### 3.2.3. MANUAL CONTROL Menu

The screenshot shows a control interface with the following elements:

- CONSIGNE** followed by three asterisks, a comma, a degree symbol, the letter C, two asterisks, and a percent sign. A callout points to the degree symbol and C, indicating the temperature set point.
- R-----** followed by a dashed line. A callout points to this field, indicating the humidity set point.
- DEPART** followed by a dashed line. A callout points to this field, indicating an option for 4 NF / NO type relays.


Callout for Temperature set point:  
Temperature set point.  
Modification of the value with key « SURFER » when symbol °C blinks.  
Press key **VALID** to confirm the value and go to the next field.

Callout for Humidity set point:  
Humidity set point.  
Modification of the value with key « SURFER » when symbol % blinks.  
Press key **VALID** to confirm the value and go to the next field.

Callout for Option:  
Option  
4 NF / NO type relays  
The state of the blinking relays can be modified using key « SURFER ».  
Symbol — corresponds to contact C R of the interface box.  
A number corresponds to contact C T of the interface box.  
The order of the relays is 1234.  
Press key to **VALID** in the state of the relays and go to the next relay or next field.

Press key **VALID** to:  
- Start the climatic chamber.  
- Go to the control screen page of the manual control.  
- Reset the cycle counter.  
Modify START with CANCEL using key « SURFER » in order to correct the set points.

### 3.2.4. MANUAL CONTROL Screen Page




You can change the set points in terms of °C, % and R by pressing the **VALID** key.

When modifying the set points, the climatic chamber operates according to the previous set points.

After around 10 seconds without any action on the controller, this device will take into account the set points displayed.


This function does not reset the cycle counter.

### 3.2.5. PROGRAMMED CONTROL Menu



CANCEL: returns to program number for another selection.  
IMMEDIATE EXECUTION: triggers off the selected program, and displays the PROGRAMMED CONTROL screen.  
DIFFERED EXECUTION: displays the data acquisition screen in view of a differed program execution. The selection is made in terms of day, hour and minute.

### 3.2.6. PROGRAMMED CONTROL Screen Page



The value of the shaded lines varies according to the SCROLLING value entered in the CUSTOMISATION menu, which can be reached through INIT.

If the SCROLL is NO: the shaded lines can be reached using key « SURFER ».


If the SCROLL is YES: the shaded lines appear automatically one after the other every 5 seconds.

### 3.2.7. PROGRAMMING Menu

Displays the program number. Use key « SURFER » to reach the program number desired.

Press **VALID** key to select the title of the program.

Press **VALID** key until the program number no longer blinks in order to reach the PROGRAM ENTRY menu.




Title corresponding to the program number.

Press **VALID** key to change the character in the title.

Keep **VALID** key pressed until the program number blinks in order to finish the entry of the title.




### 3.2.9. INIT Menu





### 3.2.10. CUSTOMISATION Menu



Use key « SURFER » to make the required line blink. Validate this line using **VALID** key and use « SURFER » key to display YES or NO. Validate once more.

At the end of this screen page, another screen page appears, giving you the possibility to adjust the controller at given temperature and hygrometry standards.

Use **STOP** key to go back to the MAIN menu.

### **3.3. Messages**

#### **DEFAUT SONDE TEMPERATURE**

The control sensor and the safety sensor measure a difference in temperature of over 3°C.

#### **DEFAUT SEUIL TEMPERATURE**

The safety sensor measures a temperature, which is beyond the MINIMUM and MAXIMUM interval.

#### **DEFAUT SUIVI RAMPE**

The change in the temperature measurements does not respect the change in set points.

#### **DEFAUT H.P.**

Triggering of the H.P. pressure meter.

#### **DEFAUT COMPRESSEUR 1**

Triggering of the circuit breaker located in the electric circuit of the compressor's fan.

#### **DEFAUT VENTILATEUR**

Triggering of the circuit breaker located in the electric circuit of the tank's fan.

#### **DEFAUT CONDENSEUR**

Triggering off the circuit breaker located in the electric circuit of the condenser's fan.

When one of these messages appears, contact our Service Department in order to validate the error.

## **4. Maintenance**

### **4.1. *General maintenance***

In normal conditions of use, the only maintenance required consists in regularly making sure that the finned condenser which cools the refrigerating unit is clean. Using a vacuum cleaner allows you to remove dust, which is detrimental to the system efficiency. You can reach the condenser through the machine RH panel.

To make sure the system operates in humid conditions correctly, you must check the cleanness of the wick, which is used for carrying out psychrometric measurements. The quality of distilled or de-mineralized water shall remain constant (no alga or impurities).

Should the climatic chamber not be used for an extended period of time in the humidity mode, we recommend that the piping system be drained completely.

### **4.2. *Calibration***

We recommend that you check once a year the calibration of the measuring chains.


To check the calibration of the controller, replace the temperature sensor with a known fixed resistor having an accuracy of at least 0.1%. Refer to a conversion table for a PT100 sensor to know the temperature value.

Use a resistor of same rating and accuracy to connect it instead of the sensor used for measuring the degree of humidity. The humidity value measured by the controller shall be 100%.

In actual practice, you just have to calibrate the temperature of the climatic chamber directly. It has the advantage of taking into account the complete measuring chain. For that purpose, you have to have a calibrated measuring chain. The calibration can be carried out at various points, and the measurement is made after temperature stabilization for 30' to 45'.


This calibration can be carried out by our company or by any other adequately equipped company or test laboratory.

# 5. User interfaces



## 6. Technical specifications

- Volume 3000 liters
- Internal dimensions (W x D x H) : 1200 x 1400 x 1800 mm
- External dimensions (W x D x H) : 1480 x 2655 x 2100 mm
- Weight: 1800kG
  
- Temperature range: 20°C to +100°C
- Stability at one point in time:  $\pm 0,3^{\circ}\text{C}$  to  $\pm 0,5^{\circ}\text{C}$
- Useful volume homogeneity:  $\pm 2^{\circ}\text{C}$
  
- Humidity range: from 8°C to 98°C between 15% to 98% (following the chart below).
- Relative humidity resolution: 1%HR
- Stability at one point in time:  $\pm 2\%$  HR ...  $\pm 3\%$  HR
- Capacitive probe



- The time to go from ambient temperature to 85°C / 95%RH is 120minutes.
- Water condenser (flow rate: 0,7 m<sup>3</sup>/h, pressure: 2 bars mini and power rejected: 5,3 kW)
- Internal light
- 1 shelf: load 120Kg
- 2 porthole diameter 100mm
- Emergency push button

## 7. Electric files



CLIMATIC

À	MODIFICATIONS	J M A	Dessine	Etudie	Dep
ORIGINAL	BIA CLIMATIC	26/04/11	L.AMORIN	AMORIN L	

Plans à consulter		Remplace Plan :

Designation  
complémentaire

# DU PONT DE NEMOURS

CLIMATIC CHAMBER HOT/COLD/HUMIDITY : CL 0-300

LE DIEDRE	FORMAT	ECHELLE	INDICE	PLANCHE
	NXA3		A	I / 37
BIA CLIMATIC			No PLAN	201_003_0

Ce plan est la propriété de la société indiquée ci-dessus et ne peut être reproduit ou communiqué sans l'autorisation de cette dernière

Realisateur XELEC

Nom : B.I.A.

Adresse : ZA LES BOUTRIES 8 RUE DE L'HAUTIL  
78700 CONFLANS STE HONORINE  
TEL : 01-34-90-22-22

**SOMMAIRE**

No Folio	Titre_G	Titre_2	Indice	Date	Visa
1	CL 0-300	CARACTERISTIC	A	26/04/11	L.AMORIN
2	CL 0-300	DISTRIBUTION 24VCC-230VAC-COMPRESSOR	A	26/04/11	L.AMORIN
3	CL 0-300	HEATING	A	26/04/11	L.AMORIN
4	CL 0-300	HUMIDITY	A	26/04/11	L.AMORIN
5	CL 0-300	FAN	A	26/04/11	L.AMORIN
6	CL 0-300	WATER PUMP	A	26/04/11	L.AMORIN
7	CL 0-300	PRESSURE SENSOR	A	26/04/11	L.AMORIN
8	CL 0-300	CAPACITIVE PROBE	A	26/04/11	L.AMORIN
9	CL 0-300	CONVERTER	A	26/04/11	L.AMORIN
10	CL 0-300	DISTRIBUTION 230VAC ET 24VCC	A	26/04/11	L.AMORIN
11	CL 0-300	DIGITAL INPUTS PLC	A	26/04/11	L.AMORIN
12	CL 0-300	DIGITAL INPUTS PLC	A	26/04/11	L.AMORIN
13	CL 0-300	DIGITAL OUTPUTS PLC	A	26/04/11	L.AMORIN
14	CL 0-300	DIGITAL OUTPUTS PLC	A	26/04/11	L.AMORIN
15	CL 0-300	ANALOG I/O PLC	A	26/04/11	L.AMORIN
16	CL 0-300	INTERFACE - RELAY	A	26/04/11	L.AMORIN
17	CL 0-300	DISPLAY	A	26/04/11	L.AMORIN
18	CL 0-300		A	26/04/11	L.AMORIN
19	CL 0-300	WIRES NUMBERS	A	26/04/11	L.AMORIN
20	CL 0-300	TERMINAL BLOCK	A	26/04/11	L.AMORIN
21	CL 0-300	XTEH TERMINAL BLOCK	A	26/04/11	L.AMORIN
22	CL 0-300	TERMINAL BLOCK	A	26/04/11	L.AMORIN
23	CL 0-300	XTHR TERMINAL BLOCK	A	26/04/11	L.AMORIN
24	CL 0-300	TERMINAL BLOCK	A	26/04/11	L.AMORIN
25	CL 0-300	XTHRTERMINAL BLOCK	A	26/04/11	L.AMORIN
26	CL 0-300	TERMINAL BLOCK	A	26/04/11	L.AMORIN
27	CL 0-300	PROBES BLOCK	A	26/04/11	L.AMORIN
28	CL 0-300	TERMINAL BLOCK	A	26/04/11	L.AMORIN
29	CL 0-300	PRESSURE SENSOR BLOCK	A	26/04/11	L.AMORIN
30	CL 0-300	TERMINAL BLOCK	A	26/04/11	L.AMORIN
31	CL 0-300	XTRES BLOCK	A	26/04/11	L.AMORIN
32	CL 0-300	MATERIAL	A	26/04/11	L.AMORIN
33	CL 0-300	NOMENCLATURE ELECTRIQUE	A	26/04/11	L.AMORIN
34	CL 0-300	NOMENCLATURE ELECTRIQUE	A	26/04/11	L.AMORIN
35	CL 0-300	NOMENCLATURE ELECTRIQUE	A	26/04/11	L.AMORIN

A

B

C

D


E

Folio **II**

Indicateur Tira **A**

N° **201\_003\_0**

CL 0-300  
SUMMARY



**BIA CLIMATIC**

26/04/11 L.AMORIN



# ELECTRICAL DRAWING

# HOT/COLD/HUMIDITY CHAMBER

## +100 A 20 Degres C

## CL 0-300

01 02 03 04 05 06 07 08 09 10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25 26 27 28 29 30 31 32 33 34 35 36 37 38 39

E \_\_\_\_\_ D \_\_\_\_\_ C \_\_\_\_\_ B \_\_\_\_\_ A \_\_\_\_\_


A	26/04/11	L. AMORIN								
		ORIGINAL								
		DATE	VISA		DATE	VISA				

**CL 0-300**  
**CARACTERISTIC**



AFFAIRE	FOLIO
<b>201_003_0</b>	<b>1</b>
LOCALISATION	ENCEINTE

01	02	03	04	05	06	07	08	09	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39
----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----



A	26/04/11	L. AMORIN	DATE	VISA
		ORIGINAL	DATE	VISA
			DATE	VISA
			DATE	VISA

**CL 0-300**  
**DISTRIBUTION 24VCC-230VAC-COMPRESSOR**







AFFAIRE	201_003_0	FOLIO	2
LOCALISATION	ENCEINTE		

COMPRESSOR  
 1.9KW 3000T/MN  
 400V

24VCC BEFORE GENERAL  
 230V BEFORE GENERAL  
 CAPACITIVE PROBE  
 PRESSURE SENSOR  
 (1008)(1009) (1006)(1007)  
 (703) (703) (818) (817) (903) (903) (903) (1003)(1003)




01	02	03	04	05	06	07	08	09	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39
----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----




HUMIDITY 4.05KW

A		26/04/11	L. AMOREN	ORIGINAL		DATE	VISA	DATE	VISA
<b>CL 0-300</b>									
<b>HUMIDITY</b>									
AFFAIRE					LOCALISATION				
201_003_0					4				
FOLIO					ENCEINTE				

01	02	03	04	05	06	07	08	09	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39
----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----



01 02 03 04 05 06 07 08 09 10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25 26 27 28 29 30 31 32 33 34 35 36 37 38 39



A		26/04/11	L. AMORIN																																							
			ORIGINAL																																							




**CL 0-300  
WATER PUMP**

AFFAIRE **201\_003\_0** FOLIO **6**  
LOCALISATION  
ENCEINTE



01	02	03	04	05	06	07	08	09	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39
----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----




A	26/04/11	L. AMORIN	DATE	VISA	DATE	VISA	CL 0-300 CAPACITIVE PROBE		AFFAIRE <b>201_003_0</b>	FOLIO <b>8</b>
									LOCALISATION ENCEINTE	

















01	02	03	04	05	06	07	08	09	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39
----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----



A	26/04/11	L. AMORIN																																															
		ORIGINAL																																															
		DATE	VISA	DATE	VISA	DATE	VISA																																										
																									<b>CL 0-300</b>										<b>DIGITAL OUTPUTS PLC</b>					<b>B.I.A. CLIMATIC</b>									
																									AFFAIRE <b>201_003_0</b>										LOCALISATION <b>ENCEINTE</b>					FOLIO <b>14</b>									



TEMPERATURE REGULATION HUMIDITY REGULATION  
TEMPERATURE SECURITY

**CL 0-300**  
**ANALOG I/O PLC**



A	26/04/11	L. AMORIN ORIGINAL	DATE	VISA
			DATE	VISA
			DATE	VISA


E

D

C

B

A




A	26/04/11	L.AMORIN	DATE	VISA	DATE	VISA
		ORIGINAL				

### CL 0-300

### INTERFACE - RELAY







A	26/04/11	L-AMORIN																																								
		ORIGINAL																																								
		DATE	VISA																																							

**CL 0-300  
DISPLAY**



01	02	03	04	05	06	07	08	09	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39
----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----

E

D

C

B

A

# GRILLES DES FILS

A	26/04/11	L-AMORIN																																																	
			ORIGINAL																																																

CL 0-300



AFFAIRE	FOLIO
201_003_0	18
LOCALISATION	
ENCEINTE	

E

D

C

B

A

0V	1	100	101	131	132	16	17	18	19	20	208	209	21
210	211	212	213	22	23	24V	3	30	300	302	303	304	31
36	37	4	44	45	5	500	501	504	505	508	509	54	6
70	71	72	73	76	77	78	79	80	81	84	85	87	88
90	91	92	93	C1	C2	C3	C4	C5	C6	I	II	III	L01
L04	L1	L11	L12	L2	L200	L21	L22	L3	L31	L32	L34	L35	L36
L41	L42	L43	L44	L45	L61	LCD1	LDG	LP1	N	N01	N1	N10	N200
N60	NCD1	NDG	NP1	UCP1	UV1	UV2	VCPI	VV1	VV2	WCPI	WV1	WV2	N30
													N40

Autres repères de fils utilisés

A 26/04/11 L-AMORIN

ORIGINAL

DATE

VISA

DATE

VISA

DATE

VISA

CL 0-300

WIRES NUMBERS



AFFAIRE

201\_003\_0

LOCALISATION

ENCEINTE

FOLIO

19

01	02	03	04	05	06	07	08	09	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39
----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----

E

D

C

B

A

# XTEH BLOCK

A 26/04/11 L-AMORIN

ORIGINAL

DATE VISA

DATE

VISA

**CL 0-300**

**TERMINAL BLOCK**



AFFAIRE

201\_003\_0


LOCALISATION

ENCEINTE

FOLIO

20

01	02	03	04	05	06	07	08	09	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39
----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----



Longueur : 120

ENCEINTE

**XTEH**

A	26/04/11	L.AMORIN
	ORIGINAL	
	DATE	VISA
	DATE	VISA

**CL 0-300**  
**XTEH TERMINAL BLOCK**



AFFAIRE	201_003_0	FOLIO	21
LOCALISATION		ENCEINTE	

01	02	03	04	05	06	07	08	09	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39
----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----

E

D

C

B

A

# XTHR BLOCK

A	26/04/11	L. AMORIN							
		ORIGINAL							
	DATE	VISA					DATE		VISA

**CL 0-300**  
**TERMINAL BLOCK**



AFFAIRE	FOLIO
201_003_0	22
LOCALISATION	
ENCEINTE	


E

D

C

B

A



ENCEINTE

Longueur : 30

A	26/04/11	L. AMORIN																																								
		ORIGINAL																																								

**CL 0-300**  
**XTHR TERMINAL BLOCK**



01	02	03	04	05	06	07	08	09	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39
----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----

E

D

C

B

A

# XTEBHR BLOCK

A 26/04/11 L-AMORIN

ORIGINAL

DATE

VISA

DATE

VISA

CL 0-300

TERMINAL BLOCK



AFFAIRE

201\_003\_0

LOCALISATION



FOLIO

24

ENCEINTE



01
02
03
04
05
06
07
08
09
10
11
12
13
14
15
16
17
18
19
20
21
22
23
24
25
26
27
28
29
30
31
32
33
34
35
36
37
38
39



A	26/04/11	L. AMORIN
	ORIGINAL	
DATE	VISA	
DATE	VISA	
DATE	VISA	
<b>CL 0-300</b>		
<b>XTHRTERMINAL BLOCK</b>		
<b>BiA</b> CLIMATIC		
AFFAIRE	201_003_0	FOLIO
LOCALISATION		25
ENCEINTE		

01	02	03	04	05	06	07	08	09	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39
----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----

E

D

C

B

A

# PROBES BLOCK

A	26/04/11	L-AMORIN				
		ORIGINAL				
	DATE	VISA	DATE	VISA		

**CL 0-300**  
**TERMINAL BLOCK**



AFFAIRE	FOLIO
201_003_0	26
LOCALISATION	
ENCEINTE	



01	02	03	04	05	06	07	08	09	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39
----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----

E

D

C

B

A

# PRESSURE SENSOR BLOCK

A 26/04/11 L. AMORIN

ORIGINAL

DATE VISA

DATE

VISA

CL 0-300

TERMINAL BLOCK



AFFAIRE

201\_003\_0

LOCALISATION

FOLIO

28

ENCEINTE



01	02	03	04	05	06	07	08	09	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39
----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----

E

D

C

B

A

# XTRES BLOCK

A 26/04/11 L-AMORIN

ORIGINAL

DATE VISA

DATE VISA

DATE VISA

**CL 0-300**

**TERMINAL BLOCK**



AFFAIRE

201\_003\_0

LOCALISATION

FOLIO

30

ENCEINTE

01	02	03	04	05	06	07	08	09	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39
----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----

E

D

C

B

A

ENCEINTE

132	1	131	2
(822)		(823)	

Longueur : 12

**CL 0-300**  
**XTRES BLOCK**



AFFAIRE	201_003_0	FOLIO
		31
		ENCEINTE

A	L-AMORIN	VISA
	ORIGINAL	
DATE	VISA	DATE





01 02 03 04 05 06 07 08 09 10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25 26 27 28 29 30 31 32 33 34 35 36 37 38 39

REPERE	Nbr	DESIGNATION	CARACTERISTIQUES	REFERENCE	FABRIQUANT
QSO	1	SWITCH	TRI 25 AMP	IMF10025	TELEMECANIQUE
QG	1	SWITCH	TETRA 25A	ICN00007	TELEMECANIQUE
QS1-QS2-QS3-QS4	4	CIRCUIT BREAKER	UNI+NEUTRE	KHC00001	TELEMECANIQUE
KM1	1	CONTACTOR	TRI 25 AMP	ICI00022	TELEMECANIQUE
GS1	1	POWER SUPPLY	24VCC 6A	IC040005	WEIDMULLER
QCP1	1	CIRCUIT BREAKER	4 A 6.3 AMP	ICJ00006	TELEMECANIQUE
GS3	1	POWER SUPPLY	24VCC 1.5A	IC0400XX	WEIDMULLER
KMC1	1	CONTACTOR	TRI 6 AMP	ICI00020	TELEMECANIQUE
CP1	1	COMPRESSOR	2.5CV 400V TRI	IEA00008	UH
RSC1-RSC2	2	STATIC CONTACTOR	UNI 25AMP 660V	ICI30001	CELDUC
RSH1-RSH2	2	STATIC CONTACTOR	UNI 25AMP 660V	ICI30001	CELDUC
QCH1	1	CIRCUIT BREAKER	TRI 6 AMP	ICJ000XX	MERLIN GERIN
QHR1	1	CIRCUIT BREAKER	TRI 10 AMP	ICJ000XX	MERLIN GERIN
EH1 A EH6	6	HEATER	1000W 230VAC	ICA00002	VULCANIC
EH7 A EH21	15	HEATER	270W 230VAC	ICA000XX	ACIM JOUANIN

A	26/04/11	L. AMORIN							
		ORIGINAL							
	DATE	VISA		DATE	VISA				

**CL 0-300**  
**NOMENCLATURE ELECTRIQUE**



AFFAIRE **201\_003\_0** FOLIO **33**  
 LOCALISATION ENCEINTE

01 02 03 04 05 06 07 08 09 10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25 26 27 28 29 30 31 32 33 34 35 36 37 38 39

REPERE	Nbr	DESIGNATION	CARACTERISTIQUES	REFERENCE	FABRIQUANT
QV1-QV2	2	CIRCUIT BREKER	0.63 A 1 AMP	ICJ00002	TELEMECANIQUE
QCD1	1	CIRCUIT BREKER	0.25 A 0.40 AMP	ICJ000XX	TELEMECANIQUE
V1-V2	2	FAN MOTOR	1/3 CV 400V TRI	ICR000XX	LS
CD1	1	FAN CONDENSEUR	22W 230VAC		UH
QSP1	1	CIRCUIT BREKER	PH +N	XXXXXXX	TELEMECANIQUE
KMP1	1	CONTACTOR	TRI 6A 24VCC	XXXXXXX	TELEMECANIQUE
P1	1	PUMP	11W 230VAC	XXXXXXX	PAN WORLD
SPEAU	1	PRESSOSTAT	LOW PRESSURE	IEI00002	JOHNNESON CONTROL
GS2	1	POWER SUPPLY	+/-12VCC - 5VCC	IC04004	COMPUTER PRODUCTS
SP1	1	PRESSOSTAT	HIGH PRESSURE	IEI00001	JOHNNESON CONTROL
CBP1	1	PRESSURE SENSOR	-0.5 A 7 BAR FOR 4-20mA		HUBA CONTROL
CHP1	1	PRESSURE SENSOR	0 A 25 BAR FOR 4-20mA		HUBA CONTROL
STH	1	THERMOSTAT	50 A 300 °C		JUMO REGULATION
Y1-YCC-Y5	3	BOBINE	24VCC 20VA	ICL00003	DANFOSS
NV1	1	LEVEL DETECTOR	1 NO	XXXXXXX	RS
TC2	1	TRANSFORMER	230VAC - 12VAC-105VA	IC000002	MAZDA
EL1-EL2	2	HALOGENE LIGHT	35W 12VAC	ICP03987	MAZDA

A	26/04/11	L. AMORIN			
		ORIGINAL			
	DATE	VISA	DATE	VISA	

CL 0-300  
NOMENCLATURE ELECTRIQUE



AFFAIRE 201\_003\_0  
LOCALISATION ENCEINTE  
FOLIO 34


REPERE	Nbr	DESIGNATION	CARACTERISTIQUES	REFERENCE	FABRIQUANT
RT1	1	PROBE	2 x PT100 A 0 DEG C	IJA00002	HEREAUS_SENSORS
RT2	1	PROBE	2 x PT100 A 0 DEG C	IJA000XX	TC_SA
CLIM-POW	1	POWER_CARD	23 INLETS / 20 OUTLETS	IBA00100	BIA
CLIM-CPU	1	PLC_CARD	8 ANALOG INLETS / 2 ANALOG OUTLETS	IBA00101	BIA
OPT	1	INTERFACEBOX	RS232		BIA
FAC1	1	DISPLAY	4 LINES OF 20 CARACTERES		BIA
CV2	1	CONVERTER	PT 100 EN 0-10V		PR ELECTRONICS
SONHR	1	SONDE CAPACITIVE	0-1V POUR 0-100 HR		VAISALA
TC3	1	TRANSFORMER	160VA P=230VAC S=24VAC		LEGRAND
EH30-EH31	2	WINDOW HEATING	24VAC 50W X 2		ANTHONY GLASS

E  
  
  
  
  
  
  
  
  
  
D  
  
  
  
  
  
  
  
  
  
C  
  
  
  
  
  
  
  
  
  
B  
  
  
  
  
  
  
  
  
  
A

A	26/04/11	L.AMOREN																																		
		ORIGINAL																																		
	DATE	VISA		DATE	VISA																															

### CL 0-300

## NOMENCLATURE ELECTRIQUE



AFFAIRE	201_003_0	FOLIO	35
LOCALISATION		ENCEINTE	